Secrt. II-27—50,006—27-10-41.

P.W (1942) Department.
(Marine)

MS SERIES.

G.O. No.	1334
	1334
Dated	4-5-1942.

[Despatch Abstract.]

Report to accompany the estimate for extending the wharf wall in south reclamation and reclaiming wharf, Mangalore Port

Estimate Rs.17,500/-

This estimate provides for constructing a wharf wall and reclaiming the land up to the drain at the south end of the south reclamation area. The wharf wall will be of dry stone with a facing of random rubble in cement mortar 1:5 and 2'-0" thick. A concrete coping 0'-6" thick at top is provided. The wall will be taken down to 9'-0" below the low water level with 2'-0" depth of concrete for foundation and the height of the wall will be 9'-0" above low water and 2'-0" above the H.W.O.S.

A revetment 1'-6" thick with gravel backing of 0'-6" will be constructed on the drain side in the south with a toe of 3'-0" by 3'-0" granite rough stone in cement mortar 1:5 taken down to 3'-0" below low water or 6'-0" below the existing bed of drain. The top of revetment will be the top level of wharf wall. The estimate provides for using the old materials available at site.

The proposals have been approved by the Port Conservancy Board and copy of the(ri) resolution is attached.

K.S. Kailasam,
S.O., Calicut.

G.Gopalacharya,
S.D.O., Calicut.

XII Comp 4 info

Executive Engineer,
Marine Division.

P.T.O.

Proceedings of the monthly meeting of the Port Conservancy Board, Mangalore, held at the Port Office, Mangalore on Thursday the 26th March 1942 at 9-30 A.M.

X. Read estimate for special repairs to north wharf wall Rs.2,500.

"A p p r o v e d"

XI. Read estimate for removing the materials at north wharf wall and stacking them at south reclamation area, Rs.1,600/-

A p p r o v e d"

XII. Read estimate for extending the wharf wall in south reclamation and reclaiming wharf, Rs.18,000/-.

A p p r o v e d

Sd. M.Karamatullah,
26-3-42.
Collector & Chairman.

C.F. 33 (c). Rg. 402 PW dt 9.2.42
1598 " 30.6.41
2971 " 8.12.41
1143 " 9.1.42

PORT Department

From (Name) W. F Ruffle Esq

Designation Presidency Port Officer, Madras,

Station Calicut.

UNDER SECRETARY TO GO
VI
29 APR 1942
PUBLIC WORKS DEPART

Received Registered 27

To

The Secretary to Government,
Public Works (Mar.) Department,
Madras at Ootacamund.

pp 3-12-42 (Issued below)

Enclosures:
1 Est. & 2 plans for refce. & kind return.

No. 718 A/42-1 dated 27th April 1942

Sir,

Port of Mangalore - Extending the South Wharf Wall and reclaiming area for Wharves - Estimate for Rs17,500/- Sanction requested.

I have the honour to forward for the sanction of Government an estimate for Rs.17,500/- received from the Executive Engineer, Marine Division, Madras for extending the South Wharf wall and reclaiming area for wharves at the port of Mangalore. The actual estimated cost is Rs.21,736 but it has been reduced to Rs.17,500/- to allow deduction of the cost of materials taken over by this department from Mr. Tarapore as per G.O.No.Ms.402 Public Works Department, dated 9-2-42 and proposed to be utilised for this work. The Executive Engineer, Marine states that this work will complete, for the present, the improvements to the South reclamation area but is not in itself a very urgent or important work.

2. Necessary provision exists in the draft Budget Estimate of the Mangalore Landing and Shipping Fund for 42-'43

'42-'43 now before Government.

3. The local Port Conservancy Board has approved the estimate.

I have the honour to be
Sir,
Your most obedient servant

28/4

Presidency Port Officer.

14/14/5
Date. Initials.

DRAFT FOR APPROVAL.

C.F. 16.
P.W(Nav).

When received for fair copying .. ✓
When copied ..
When examined..
When signed ..
When despatched.

SUBJECT :—

Ports - Mangalore - Extending the South wharf wall & reclaiming area for wharves. Estimate for Rs. 17,500/- Sanctioned.

READ AGAIN ..... dated 19

" " " " 19

READ *ALSO* :—

e. No. 227 VI/45 From the P.P.O, Calicut, No. 718 A/42-1 dated 8 27.4.1942. of

" ..... " ..... " ..... " 19

" ..... " ..... " ..... " 19

Order ~~Resolution~~ Ms. No. 1334, dated 14. 5. 1942

pp 3-12 of vide orders on p 1 of

The Govt Sanction the estimate amounting to Rs. 17,500/- (Seventeen thousand five hundred) for extending the South wharf wall & reclaiming area for wharves at the port of Mangalore.

The expenditure should be met from the provision made for the work in the R.F. of the Mangalore L & S. Fund for 1942-43. para 2 on pp 1-2 of

Typed with check 16/5 Dne 11.5.42.

To the P.P.O with 11/5
(Plans below) Plans & estimates (pp 5-12 of
the Exor of L.F. in original
Accts (Plans below)
(copy for file)

P.W(Hbr)

Ports - Mangalore - Extending the South wharf wall & reclaiming area for wharves: Estimate for Rs. 17,500/-

C.no. 227.VI/42 From the P.P.O, Calicut. No. 718A/42-1 dt 27.4.1942.

To us

plef pp 3-12 cf

The P.P.O has forwarded for the sanction of Govt an estimate for Rs. 17,500 received from the E.E. Harima Dn. for extending the South wharf wall & reclaiming area for wharves at the port of Mangalore. This estimate does not include the cost of materials collected for the work of reconstruction & realignment of north wharf wall which has been deferred in Go. Ms. No. 2971 P.W.D. 8.12.41. The materials (in part) are proposed to be utilised for the present work - vide also para 4 of Go. Ms. No. 402 P.W.D. dt 9.2.1942. The E.E. Harima Dn is reported to have stated that the proposed work will complete for the present, the improvements to the South reclamation area, but is not in itself a very urgent or important work. The local P.C. Board has approved the estimate & necessary provision has been made in the Mangalore Dist. Funds for the current year. The proposal does not seem to involve the use of any steel. For orders whether the estimate may be sanctioned in view of 'A' or deferred in view of 'B' above

The actual estimate is 21,736
The estimate 17,500
4,236.

(X) (N)

May be sanctioned.

42

SECRETARIAT TO GOVERNMENT
9 MAY 1942
PUBLIC WORKS DEPARTMENT

To U.S.

with reference to orders on plants, a draft order sanctioning his estimate is submitted (removed for office).

P.S. 42

11/5 Extract Economic No. 1324 PW (War) 2-14-5-42].